

# FIRE SUPPRESSION INSPECTION PROCEDURES



---

# Contractor Plan Submittal

**Complete Fire  
Suppression Permit  
Application  
(see Appendix Item 'A')**



**4 Sets for  
BSD review and  
1 set for  
CFD review**



**Upon Approval  
Contractor is  
Returned 2 Sets  
with Permit**



**Ready For  
System  
Installation**

---

# System Installation



System is to be installed in accordance with all approved construction documents.

---

# OBBC

---

System must be installed as code compliant in accordance with all applicable NFPA standards and building codes.



---

# Scheduling Inspections



Contractor completes and faxes a Fire Protection Request Form (see Appendix Item 'B') to:  
(614) 645-8358

Limited Area, Modified Systems affecting 20 heads or less and final inspections of all systems will be scheduled the next business day if requested prior to 10:00 am.

**NOTE:** Lead-time for scheduling Fire Suppression inspections is identified in CIC #3 (see Appendix Item 'C')

---

All New and Modified Systems affecting more than 20 Heads shall be tested at 200 PSI without loss of pressure for 2 hours.


Exception: modifications that cannot be isolated shall not require testing in excess of system working pressure.

**Inspections requested will be scheduled on the date requested or closest available. A return call will be made within 2 working days upon receipt of fax to confirm date and time of test.**

**One inspection trip allowing up to one-hour of inspection time will be deducted from the permit to schedule an inspection. For inspections exceeding one-hour, the test will continue but an additional trip for each additional hour will be assessed against the permit and no final approval will be granted until the outstanding fee is paid.**

---

# Inspection Of Limited Area Or Modified Systems Having 20 Heads Or Less



- Inspector reviews construction documents for approvals and completeness.
- Inspector verifies that all piping and devices are according to approved documents (109.1 OBC)
- Inspector will give final approval upon code compliance of all system components.

---


# Inspection Of New Or Modified Systems Having More Than 20 Heads




- Inspector reviews construction documents for approvals and completeness.
- Inspector verifies pressure gauge for 200PSI and begins the 2-hour Hydrostatic test.
- Inspector verifies that all piping and devices are according to approved documents (109.1 OBC)
- If no loss of pressure and no violations were observed, the inspector will sign the building permit.
- If violations including loss of pressure were observed, the inspector will leave a Fire Suppression Inspection Form identifying the violations.

---

## Inspection Of New Or Modified Systems Having More Than 20 Heads



- If system piping is to be covered by ceilings or other building finishes then an additional inspection will be necessary to verify proper sprinkler head placement and signage is in place.



- If sprinkler piping is to be painted, it must be inspected by the building inspector prior to covering to ensure the correct type of pipe was installed.

# Inspection Of New Or Modified Systems Having More Than 20 Heads

**HYDRAULIC SYSTEM**

This building is protected by a Hydraulically Designed Automatic Sprinkler System

Date Installed	7 2007
Location	ARENA CROSSING – RETAIL
No. of Sprinklers	10
Basis of Design	
1. Density	20
2. Designed area of discharge	1500
System Design	
1. Water flow rate	995
2. Residual pressure at the base of the riser	92.1
Installed by	ACME FIRE COMPANY




The fire alarm acceptance test and approval of all newly installed tamper switches, flow or alarm devices must be completed prior to scheduling a final suppression inspection.

- Contractor must provide a completed material and test certificate. (see Appendix Item 'D' – Contractor's Material and Test Certificate for Aboveground Piping)
- Inspector reviews construction documents for approvals and completeness.
- Inspector will verify the installation of the Hydraulic calculation sign, stock of spare sprinkler heads in cabinet and the general information sign.  
**Note:** spare special sized dry pendant heads are not required in cabinet
- Inspector will check for signage on all valves



---

# Inspection Of New Or Modified Systems Having More Than 20 Heads



- Inspector will verify head type and placement.
- Inspector will check to ensure a ceiling is provided for pendant heads when applicable and escutcheon plates are installed.
- Inspector will check for obstructions to the sprinkler heads.
- If violations were observed during the inspection the inspector will leave a fire suppression inspection form on site identifying the corrections needed. If no violations were observed the inspector will sign the building permit under fire suppression final.





# Fire Protection Inspection Request Form



City of Columbus

Development Department

Building Services Division

## FIRE PROTECTION INSPECTION REQUEST FORM

<b>JOBSITE ADDRESS</b>	
------------------------	--

<b>DATE REQUESTED</b>		<b>CONFIRMED DATE / TIME</b>	
-----------------------	--	------------------------------	--

- FIRE ALARM WITNESS TEST
- FIRE SUPPRESSION HYDROSTATIC TEST
- HVAC SYSTEM TEST  Regular Business Hours
- ELECTRICAL SYSTEM TEST  After Regular Business Hours
- ROUGH SUPPRESSION
- FINAL SUPPRESSION

SOFT ACCOUNT #	PIN #	AUTHORIZED SIGNATURE OF ACCOUNT
----------------	-------	---------------------------------

PERMIT NUMBER FIRE ALARM # FIRE SUPPRESSION #	CONTRACTOR INFORMATION CONTACT PERSON	CONTACT PHONE NUMBER

#	Fire Alarm Devices	#	Fire Alarm Devices	#	HVAC Devices	#	Electrical Systems
	Manual Pull Stations		Egress Control Devices		Smoke Control System		Generator test
	A/V Units		Hold Open Devices		Duct Detectors		Fire Pump Test
	Smoke/Heat Detectors		Fire Shutter		Smoke Dampers	<b>Fire Suppression Systems</b>	<b>Fire Suppression Systems</b>
	Elevator Recall		Sprinkler Flow Alarm		Hood/Suppression Alarm		
	Electric Strikes		Sprinkler Tamper Device		FM 200		Sprinkler Heads
	Other:		Other:		Stairway Pressurization		Risers
					Other:		

**Comments:**

FIRE PROTECTION COMPANY NAME			
F/A INSTALLER SIGNATURE		DATE	
F/S INSTALLER SIGNATURE		DATE	

FP INSPECTION REQUEST FORM  
3/25/2008  
DG

# Aboveground Piping Certificate (page 1)

<b>Contractor's Material and Test Certificate for Aboveground Piping</b>																		
<b>PROCEDURE</b> Upon completion of work, inspection and tests shall be made by the contractor's representative and witnessed by the property owner or their authorized agent. All defects shall be corrected and system left in service before contractor's personnel finally leave the job.																		
A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners, and contractor. It is understood the owner's representative's signature in no way prejudices any claim against contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances.																		
Property name						Date												
Property address																		
Plans	Accepted by approving authorities (names)																	
	Address																	
	Installation conforms to accepted plans						<input type="checkbox"/> Yes <input type="checkbox"/> No											
	Equipment used is approved If no, explain deviations						<input type="checkbox"/> Yes <input type="checkbox"/> No											
Instructions	Has person in charge of fire equipment been instructed as to location of control valves and care and maintenance of this new equipment? If no, explain									<input type="checkbox"/> Yes <input type="checkbox"/> No								
	Have copies of the following been left on the premises?									<input type="checkbox"/> Yes <input type="checkbox"/> No								
	1. System components instructions						<input type="checkbox"/> Yes <input type="checkbox"/> No											
	2. Care and maintenance instructions						<input type="checkbox"/> Yes <input type="checkbox"/> No											
3. NFPA 25										<input type="checkbox"/> Yes <input type="checkbox"/> No								
Location of system																		
Supplies buildings																		
Sprinklers	Make		Model		Year of manufacture		Orifice size		Quantity		Temperature rating							
Pipe and fittings																		
Type of pipe _____																		
Type of fittings _____																		
Alarm valve or flow indicator	Alarm device						Maximum time to operate through test connection											
	Type		Make		Model		Minutes		Seconds									
Dry pipe operating test	Dry valve						Q. O. D.											
	Make		Model		Serial no.		Make		Model		Serial no.							
	Time to trip through test connection <sup>a,b</sup>		Water pressure		Air pressure		Trip point air pressure		Time water reached test outlet <sup>a,b</sup>		Alarm operated properly							
	Minutes		Seconds		psi		psi		psi		Minutes		Seconds		Yes		No	
	Without Q.O.D.																	
With Q.O.D.																		
If no, explain																		
© 2006 National Fire Protection Association										NFPA 13 (p. 1 of 3)								

<sup>a</sup> Measured from time inspector's test connection is opened  
<sup>b</sup> NFPA 13 only requires the 60-second limitation in specific sections

# Aboveground Piping Certificate (page 2)

Deluge and preaction valves	Operation <input type="checkbox"/> Pneumatic <input type="checkbox"/> Electric <input type="checkbox"/> Hydraulics							
	Piping supervised <input type="checkbox"/> Yes <input type="checkbox"/> No				Detecting media supervised <input type="checkbox"/> Yes <input type="checkbox"/> No			
	Does valve operate from the manual trip, remote, or both control stations? <input type="checkbox"/> Yes <input type="checkbox"/> No							
	Is there an accessible facility in each circuit for testing? <input type="checkbox"/> Yes <input type="checkbox"/> No						If no, explain	
	Make	Model	Does each circuit operate supervision loss alarm?		Does each circuit operate valve release?		Maximum time to operate release	
		Yes	No	Yes	No	Minutes	Seconds	
Pressure reducing valve test	Location and floor	Make and model	Setting	Static pressure		Residual pressure (flowing)		Flow rate
				Inlet (psi)	Outlet (psi)	Inlet (psi)	Outlet (psi)	Flow (gpm)
Test description	<p><b>Hydrostatic:</b> Hydrostatic tests shall be made at not less than 200 psi (13.6 bar) for 2 hours or 50 psi (3.4 bar) above static pressure in excess of 150 psi (10.2 bar) for 2 hours. Differential dry-pipe valve clappers shall be left open during the test to prevent damage. All aboveground piping leakage shall be stopped.</p> <p><b>Pneumatic:</b> Establish 40 psi (2.7 bar) air pressure and measure drop, which shall not exceed 1½ psi (0.1 bar) in 24 hours. Test pressure tanks at normal water level and air pressure and measure air pressure drop, which shall not exceed 1½ psi (0.1 bar) in 24 hours.</p>							
Tests	All piping hydrostatically tested at _____ psi (____ bar) for _____ hours						If no, state reason	
	Dry piping pneumatically tested <input type="checkbox"/> Yes <input type="checkbox"/> No							
	Equipment operates properly <input type="checkbox"/> Yes <input type="checkbox"/> No							
	Do you certify as the sprinkler contractor that additives and corrosive chemicals, sodium silicate or derivatives of sodium silicate, brine, or other corrosive chemicals were not used for testing systems or stopping leaks? <input type="checkbox"/> Yes <input type="checkbox"/> No							
	Drain test	Reading of gauge located near water supply test connection: _____ psi (____ bar)				Residual pressure with valve in test connection open wide: _____ psi (____ bar)		
Underground mains and lead-in connections to system risers flushed before connection made to sprinkler piping								
Verified by copy of the Contractor's Material and Test Certificate for Underground Piping <input type="checkbox"/> Yes <input type="checkbox"/> No						Other Explain		
Flushed by installer of underground sprinkler piping <input type="checkbox"/> Yes <input type="checkbox"/> No								
If powder-driven fasteners are used in concrete, has representative sample testing been satisfactorily completed? <input type="checkbox"/> Yes <input type="checkbox"/> No						If no, explain		
Blank testing gaskets	Number used		Locations				Number removed	
Welding	Welding piping <input type="checkbox"/> Yes <input type="checkbox"/> No							
	If yes . . .							
	Do you certify as the sprinkler contractor that welding procedures used complied with the minimum requirements of AWS B2.1, ASME Section IX <i>Welding and Brazing Qualifications</i> , or other applicable qualification standard as required by the AHJ?						<input type="checkbox"/> Yes <input type="checkbox"/> No	
	Do you certify that all welding was performed by welders or welding operators qualified in accordance with the minimum requirements of AWS B2.1, ASME Section IX <i>Welding and Brazing Qualifications</i> , or other applicable qualification standard as required by the AHJ?						<input type="checkbox"/> Yes <input type="checkbox"/> No	
Do you certify that the welding was conducted in compliance with a documented quality control procedure to ensure that (1) all discs are retrieved; (2) that openings in piping are smooth, that slag and other welding residue are removed; (3) the internal diameters of piping are not penetrated; (4) completed welds are free from cracks, incomplete fusion, surface porosity greater than 1/16 in. diameter, undercut deeper than the lesser of 25% of the wall thickness or 1/2 in.; and (5) completed circumferential butt weld reinforcement does not exceed 3/2 in.?						<input type="checkbox"/> Yes <input type="checkbox"/> No		
© 2006 National Fire Protection Association <span style="float: right;">NFPA 13 (p. 2 of 3)</span>								

