I. APPLICATION

THIS SPECIFICATION APPLIES TO THE REMOVAL OF EXISTING STREET LIGHTING MATERIAL FROM A PROJECT THAT IS NOT INTERNED TO BE RE-USED. ALL MATERIAL TO BE REMOVED BELONGS TO THE CITY OF COLUMBUS, DIVISION OF POWER (DOP). THE CONTRACTOR IS TO DISPOSE OF ALL STREET LIGHTING MATERIAL REMOVED FROM A PROJECT WITH THE EXCEPTION OF SPECIFIC ITEMS AS NOTED IN THE CONTRACT DRAWINGS.

II. REMOVAL

THE EXISTING SYSTEM SHALL BE REMOVED AND DISASSEMBLED AS SHOWN ON THE DRAWINGS AND AS INDICATED IN THE FIELD BY THE ENGINEER. THE REMOVAL SHALL CONSIST OF ANY OR ALL OF THE FOLLOWING ITEMS:

- 1. STREET LIGHT POLES AND MAST ARMS.
- 2. STREET LIGHT LUMINAIRES AND LAMPS.
- 3. CONDUIT AND UNDERGROUND CABLE (THE CONTRACTOR NEED NOT REMOVE THE EXISTING DIRECT BURIED SERIES LIGHTING CABLE WHERE THE SAME CAN BE ABANDONED IN PLACE).
- 4. PULL BOXES.
- 5. REMOVAL OF CONCRETE FOUNDATIONS IS NOT A PART OF THIS SPECIFICATION. THE CONCRETE FOUNDATION REMOVAL IS BID AS A SEPARATE ITEM UNDER MIS-900 CONCRETE FOUNDATION REMOVAL.
- 6. CONTROLLERS
- 7. MISCELLANEOUS HARDWARE.

LUMINAIRES AND LUMINAIRE WIRES ARE TO BE REMOVED FROM FROM THE MOUNTING ARMS PRIOR TO DELIVERY TO THE DIVISION OF POWER. LUMINAIRE MOUNTING ARMS ARE TO BE REMOVED FROM THE POLES.

THE CONTRACTOR WILL BE REQUIRED TO MAKE CONNECTIONS TO ASSURE THE CONTINUED OPERATION OF THE ADJACENT STREET LIGHTS NOT TO BE REMOVED IN THIS PROJECT.

FOR ANY LOCATION THAT HAS A METER INSTALLED AND SERVICE IS DISCONNECTED, THE CONTRACTOR IS RESPONSIBLE FOR MAKING ARRANGEMENTS TO RETURN THE METER AND ANY ASSOCIATED EQUIPMENT TO THE APPROPRIATE AGENCY (DOP / AEP / SCP).

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO SALVAGED MATERIALS DUE TO IMPROPER METHODS USED OR CARELESSNESS AND SHALL REPLACE SUCH MATERIALS AT NO ADDITIONAL COST TO THE CITY.

STEEL, ALUMINUM, OR FIBERGLASS LIGHT POLES IN SATISFACTORY, REUSABLE CONDITION SHALL BE RETURNED TO THE DIVISION OF POWER (DOP). ALL OTHER STREET LIGHTING MATERIAL REMOVED SHALL BE DISPOSED OF BY THE PROJECT, UNLESS OTHERWISE NOTED ON THE CONTRACT DRAWINGS, OR AS DIRECTED BY THE ENGINEER. SALVAGED MATERIALS SHALL BE DELIVERED TO THE DIVISION OF POWER DISTRIBUTION WAREHOUSE AT 3500 INDIANOLA AVE. COLUMBUS, OHIO. THE DATE AND TIME OF DELIVERY IS TO BE COORDINATED WITH THE DIVISION OF POWER PROJECT MANAGER. ALL MATERIAL MUST BE CHECKED IN BY STOREROOM PERSONNEL BEFORE IT IS UNLOADED.

III. SITE RESTORATION

SITE RESTORATION SHALL BE COMPLETED PER CMS SECTION 104.07, AS WELL AS ITEM 659 AS NOTED. SITE RESTORATION IS CONSIDERED TO BE A PART OF THIS ITEM, AND NO ADDITIONAL PAYMENT WILL BE MADE OUTSIDE THIS SPECIFICATION.

IV. BASIS OF PAYMENT

ITEM UNIT DESCRIPTION

MIS-902 LUMP SUM EXISTING UNDERGROUND SYSTEM REMOVAL

DEPARTMENT OF PUBLIC UTILITIES - DIVISION OF POWER CITY OF COLUMBUS, OHIO

EXISTING UNDERGROUND

MIS-902

EXISTING UNDERGROUNI
SYSTEM REMOVAL

DRAWN	BY: SAW	DATE:	12/21/23	
SCALE:	NONE	SHEET:	1 OF 1	902